


Greening Richmond Public Libraries


IMPROVING THE HEALTH OF THE JAMES RIVER BY REDUCING STORMWATER POLLUTION

Hull Street Branch Library

1400 Hull Street Road, Richmond, 23224



SITE PLAN APPROVED
Kenn J. Vanck
 DIRECTOR 01/22/2026



VICINITY MAP
 SCALE: 1"=2000'(±)

E+S STATISTICS	
EROSION + SEDIMENT CONTROL MEASURES	QUANTITY
CONSTRUCTION ENTRANCE	N/A (SEE NOTE)
SILT FENCE	192 L.F.
STORM DRAINAGE ITEMS	
QUANTITY	
6" HDPE PERF. UNDERDRAIN PIPING	34 L.F.
6" HDPE OVERFLOW PIPING	5 L.F.
LOT STATISTICS	
SQUARE FEET	
TOTAL LOT AREA	13,155 SF
AMOUNT OF IMP. SURFACE AREA	12,371 SF
AMOUNT OF PER. SURFACE AREA	3,441 SF
AMOUNT OF LAND DISTURBANCE	6,417 SF=0.15 AC
SEWER DESIGNATION	
M54	YES X NO
COMBINED SEWER (CSS)	X YES NO
BAY DESIGNATION	
CHESAPEAKE BAY AREA	YES X NO
IF YES,	RMA RPA

I, Claire M. Smith, PE, LEED AP certify that the information above is correct.
 Signed: *Claire M. Smith* Date: December 8, 2025
 Preparer's Seal/Stamp

NOTE: ALL QUANTITIES LISTED ARE FOR REVIEW PURPOSES ONLY. CONTRACTOR SHALL PERFORM THEIR OWN TAKE OFF FOR CONSTRUCTION PURPOSES

Stormwater Management Facility Data		Project: Greening Hull Street Library		Date: 9/16/2025										
Stormwater Management Facility Type	Stormwater Management Facility Structure Description	Stormwater Management Facility Structure Number	Location		Acres Treated By Facility			Pollutant Removal, lbs			Runoff captured, acre-feet	HUC (6th order) Of Location Of Facility	Impaired Water Segment To Which Facility Discharges	Ownership Of Facility (Public/Private)
			Latitude	Longitude	Impervious Acres	Pervious Acres	Total Acres	TP	TN	TSS				
Urban BioRetention Basin	BioRetention Basin	Basin #1	37.5197	-77.4456	0.03	0.01	0.04	0.02	0.22	-	0.002	JL01	James River - Almond Creek	Public
Micro Infiltration	Artificial Turf	Basin #2	37.5195	-77.4454	0.03	0.01	0.04	0.02	0.29	-	0.002	JL01	James River - Almond Creek	Public
Micro Infiltration	Pervious Block Pavers	Basin #3	37.5194	-77.4455	0.03	0.02	0.05	0.02	0.22	-	0.002	JL01	James River - Almond Creek	Public

SHEET INDEX

#	Sheet Title
0	Cover Sheet
1	Existing Conditions & Demolition Plan
2	Layout Plan
3	Grading Plan
4	Details
5	Details
6	Planting Plan for Volunteers
7	Notes
8	Additional Notes & Details

PROJECT DATA

OWNER:
 CITY OF RICHMOND PUBLIC WORKS
 900 E. BROAD STREET
 RICHMOND, VA 23219

DEVELOPER:
 JAMES RIVER ASSOCIATION
 16 SOUTH 17TH STREET, SUITE 100
 RICHMOND, VA 23219
 CONTACT: JUSTIN DOYLE
 PHONE: 804.788.8811
 EMAIL: JDOYLE@THEJAMESRIVER.ORG

LANDSCAPE ARCHITECT:
 FOUR WINDS DESIGN, LC
 705 LIBBIE AVENUE
 RICHMOND, VA 23226
 CONTACT: DREW HARRIGAN
 PHONE: 804.920.5878
 EMAIL: DREW@FOURWINDSDESIGN.COM

CIVIL ENGINEER:
 GRADIENT, PC
 1406 LABURNUM PARK BOULEVARD
 RICHMOND, VA 23227
 CONTACT: CLAIRE SMITH SHIRLEY, PE, LEED AP
 PHONE: 804.399.0500
 EMAIL: CLAIRE@GRADIENTENVIRONMENT.COM

CITY STANDARD PROJECT NOTES:
 PROPERTY ADDRESS: 1400 HULL STREET
 ZONING: B-5
 MAP REFERENCE #: S0000152012
 MASTERPLAN LUD: COMMUNITY MIXED USE
 CITY COUNCIL DISTRICT: 6 (MANCHESTER DISTRICT)

PROJECT SUMMARY: EXTERIOR LANDSCAPE IMPROVEMENTS
EXISTING USE: LIBRARY
PROPOSED USE: LIBRARY
ACREAGE: 0.302 ACRES
BUILDINGS: 1 EXISTING BUILDING
PARKING: 5 SPACES PROPOSED


HUC CODE: 020802060101
 JL01 JAMES RIVER-ALMOND CREEK

RELATED PERMITS

RESMP PERMIT
 WORK-IN-STREET PERMIT

NOTE:
 THIS SITE DOES NOT LIE WITHIN A CHESAPEAKE BAY RMA OR RPA. THIS SITE LIES WITHIN THE CITY'S COMBINED SEWER SERVICES AREA.

CITY APPROVALS



Cover Sheet
 For construction



GRADIENT
 1406 Laburnum Park Boulevard
 Richmond, VA 23227
 804.399.0500



Greening Richmond Public Libraries

IMPROVING THE HEALTH OF THE JAMES RIVER BY REDUCING STORMWATER POLLUTION

Hull Street Branch Library

1400 Hull Street Road, Richmond, 23224

LEGEND

- BOLLARD
- △ E-BL-S
- ⊗ GAS METER
- Ⓣ TELE. PED.
- ⊕ TREE
- ⊕ FIRE HYDRANT
- ⊙ BUSH
- ⊙ TRAFFIC LIGHT POLE
- ⊕ ADA PARKING
- ⊗ SEWER CLEAN OUT
- ⊕ ELEC. BOX or SUBPANEL
- ⊕ STORM MH
- ⊕ UTILITY POLE
- ⊗ IRRIGATION BACKFLOW
- ⊕ PREVETER
- WATER TESTING STATION

- U.G. WATER
- U.G. GAS
- O.H. ELECTRIC

- CONCRETE

— Main sewer line


Existing Trees & Shrubs To Be Preserved:

Existing Trees To Be Removed:

Pavement To Be Removed:

DATUM
HORZ.: NAD83
VERT.: NAVD88

Erosion & Sediment Control



SILT FENCE
NO SCALE

NOTES

THE EXISTENCE AND LOCATION OF UNDERGROUND UTILITIES ARE ONLY PARTIALLY SHOWN ON THIS PLAN, CONTACT MISS UTILITY.

CONTRACTOR TO ASSUME ALL RESPONSIBILITY FOR CONSTRUCTION METHODS EMPLOYED AND FIELD VERIFY ALL DIMENSIONS. ISSUES AND CONCERNS SHALL BE REPORTED TO FOUR WINDS.

CONTRACTOR TO ENSURE POSITIVE DRAINAGE AWAY FROM ALL BUILDINGS AT ALL TIMES DURING THE DEMOLITION AND BUILDING PROCESS.

NO PUBLIC THOROUGHFARES INCLUDING SIDEWALKS SHALL BE BLOCKED DURING DEMOLITION OR CONSTRUCTION WITHOUT PROPERLY DISPLAYED MUNICIPALITY PERMITS. NO HOLES SHALL BE LEFT OPEN OVERNIGHT WITHOUT SECURING PERIMETER FENCING OR INSTALLING CAUTION TAPE AROUND THE HOLE.

CONTRACTOR TO OBTAIN ALL BUILDING PERMITS, SOIL STUDIES, AND STRUCTURAL DETAILS AS REQUIRED BY THE MUNICIPALITY.

CONTRACTOR TO MAINTAIN LAMINATED "USE OTHER ENTRANCE FROM PARKING LOT" AT EACH SIDE OF THE FRONT ENTRY PLAZA MOUNTED ON EITHER THE SILT FENCE OR A POST. THE PROJECT PLANS DISPLAY BOARD WILL BE PROVIDED AND INSTALLED BY JRA BUT CONTRACTOR SHALL TAKE CARE NOT TO DISTURB IT DURING CONSTRUCTION.

IRRIGATION SYSTEM BY RICHMOND IRRIGATION AND MANAGED BY LANDSCAPE ARCHITECT. FOLLOW CONDUIT LOCATIONS AND SALVAGE EXISTING COMPONENTS WHERE POSSIBLE DURING DEMOLITION.

CONTRACTOR TO DOCUMENT DEPTHS OF BASIN EXCAVATION AND EXPLORATORY EXCAVATION (STORMWATER INFRASTRUCTURE EXPOSURE) WITH PHOTOS IN REAL TIME. UPLOAD TO DROPBOX WITH LINK PROVIDED BY LANDSCAPE ARCHITECT.

FINISH GRADE OF ALL PLANTING BEDS SHALL BE LEFT 5" BELOW MASONRY FINISH ELEVATION OF PROPOSED AND EXISTING PAVING EXCEPT WHERE NOTED.

ALL TREES TO BE MECHANICALLY REMOVED, NOT GROUND

NO MATERIALS OR MACHINES MAY BE STORED ON SITE.

THIS DRAWING PRINTS TO SCALE ON 24 X 36" PAPER AND SHOULD BE PRINTED IN COLOR. DO NOT USE NOT-TO-SCALE OR BLACK AND WHITE DRAWINGS FOR FIELD WORK OR CONSTRUCTION.

UPON BID AWARD CONTRACTOR'S PROJECT MANAGER, FOREMAN, AND/OR SITE SUPERVISOR SHALL ATTEND A MEETING ON SITE FOR DRAWING REVIEW AND PROJECT EXPECTATIONS.


Construction Access Notes:

Due to the urban nature and selective demolition of the site, all site access will be from adjacent roadways and alleys.

- Installation of a Construction Entrance is not feasible. Contractor shall minimize sediment runoff from site at all times during construction. Any sedimentation of adjacent sidewalks, curb & gutter and roadways will be cleaned immediately as required by the minimum standards.
- Contractor shall provide all required Work Area Protection signage and necessary road closures shall be coordinated with and permitted by DFW.



SITE PLAN APPROVED
Kenn J. Vack
DIRECTOR 01/22/2026



*THIS PLAN HAS BEEN REVIEWED AND APPROVED BY CITY ARBORISTS

For Permit

Revision Block	
Revised per city comment 11.18.25	

Date: 12-8-25
Sheet 1 of 7



Greening Richmond Public Libraries

IMPROVING THE HEALTH OF THE JAMES RIVER BY REDUCING STORMWATER POLLUTION

Hull Street Branch Library

1400 Hull Street Road, Richmond, 23224

LEGEND

- BOLLARD
- △ E-BL-S
- ⊕ GAS METER
- Ⓣ TELE. PED.
- ⊗ TREE
- ⊕ FIRE HYDRANT
- ⊙ BUSH
- ⊙ TRAFFIC LIGHT POLE
- ⊙ ADA PARKING
- ⊙ SEWER CLEAN OUT
- ⊙ ELEC. BOX
- ⊙ STORM MH
- ⊕ UTILITY POLE
- ⊗ IRRIGATION BACKFLOW PREVENTER
- WATER TESTING STATION
- ⊗ ELECTRICAL JUNCTION BOX

- U.G. WATER
- U.G. GAS
- O.H. ELECTRIC
- CONCRETE



- ### Erosion & Sediment Control
- Silt Fence, see detail
 - 8" Silt Soxx, (2) see detail
 - Limits of Disturbance

Proposed Elements, see details

- Pervious Pavers
- Concrete
- Artificial Turf
- Bioretention Basin

NOTES

THE EXISTENCE AND LOCATION OF UNDERGROUND UTILITIES ARE ONLY PARTIALLY SHOWN ON THIS PLAN. CONTACT MISS UTILITY.

CONTRACTOR TO ASSUME ALL RESPONSIBILITY FOR CONSTRUCTION METHODS EMPLOYED AND FIELD VERIFY ALL DIMENSIONS. ISSUES AND CONCERNS SHALL BE REPORTED TO FOUR WINDS.

CONTRACTOR TO ENSURE POSITIVE DRAINAGE AWAY FROM ALL BUILDINGS AT ALL TIMES DURING THE DEMOLITION AND BUILDING PROCESS.

NO PUBLIC THOROUGHFARES INCLUDING SIDEWALKS SHALL BE BLOCKED DURING DEMOLITION OR CONSTRUCTION WITHOUT PROPERLY DISPLAYED MUNICIPALITY PERMITS. NO HOLES SHALL BE LEFT OPEN OVERNIGHT WITHOUT SECURING PERIMETER FENCING OR INSTALLING CAUTION TAPE AROUND THE HOLE.

CONTRACTOR TO OBTAIN ALL BUILDING PERMITS, SOIL STUDIES, AND STRUCTURAL DETAILS AS REQUIRED BY THE MUNICIPALITY.

IRRIGATION SYSTEM BY RICHMOND IRRIGATION AND MANAGED BY LANDSCAPE ARCHITECT. FOLLOW CONDUIT LOCATIONS AND SALVAGE EXISTING COMPONENTS WHERE POSSIBLE DURING DEMOLITION.

CONTRACTOR TO ALLOW ONE WEEK IN PROJECT SCHEDULE FOR ROUGH IN OF IRRIGATION SYSTEM. CONTRACTOR MAY BE ON SITE BUT MUST STAY OUT OF THE WAY (ALIGN WITH CONCRETE POUR/MASONRY/PAVERS, ORNAMENTAL GRAVEL, ARBOR SCHEDULE, ETC).

CONTRACTOR TO DOCUMENT DEPTHS OF BASIN EXCAVATION AND EXPLORATORY EXCAVATION (STORMWATER INFRASTRUCTURE EXPOSURE) WITH PHOTOS IN REAL TIME. UPLOAD TO DROPBOX WITH LINK PROVIDED BY LANDSCAPE ARCHITECT.

FINISH GRADE OF ALL PLANTING BEDS SHALL BE LEFT 5" BELOW MASONRY FINISH ELEVATION OF PROPOSED AND EXISTING PAVING EXCEPT WHERE NOTED.

ALL DEBRIS SHALL BE REMOVED FROM THE SOIL IN ALL PLANTING AREAS.

CONTRACTOR TO PERFORM SITE WALK THROUGH WITH LANDSCAPE ARCHITECT, REPRESENTATIVES FROM THE JAMES RIVER ASSOCIATION, AND RICHMOND PUBLIC LIBRARIES LEADERSHIP JUST BEFORE VOLUNTEER WORK DAYS FOR PUNCH LIST.

CONTRACTOR TO PERFORM SECONDARY WALK THROUGH WITH LANDSCAPE ARCHITECT AT 12 MONTHS FROM COMPLETION TO IDENTIFY AREAS FOR RE-SEEDING AND ADDITION OF TOPSOIL IN AREAS OF SETTLEMENT ON THE MOUND. THIS SHALL BE BILLED AS TIME AND MATERIALS AT THE TIME OF WALK THROUGH AS A SEPARATE PROJECT.


ADDITIONAL DIMENSIONS AND LAYOUT NOTATION PROVIDED WITH CONSTRUCTION DOCUMENTS.

CONTRACTOR TO SUBMIT SPEC SHEET FOR THE BIORETENTION MEDIA AND PROVIDE A MOCK-UP OF THE CONCRETE FINISHING FOR ALL CONCRETE FINISHING. CONTRACTOR TO SUBMIT SHOP DRAWINGS FOR RAILINGS AT ADA RAMP.

THE PARKING LOT BUMPER BLOCKS SHALL BE RE-INSTALLED AS THEY ARE CURRENTLY INSTALLED.

THIS DRAWING PRINTS TO SCALE ON 24 X 36" PAPER AND SHOULD BE PRINTED IN COLOR. DO NOT USE NOT-TO-SCALE OR BLACK AND WHITE DRAWINGS FOR FIELD WORK OR CONSTRUCTION.



UPON BID AWARD CONTRACTOR'S PROJECT MANAGER, FOREMEN, AND/ OR SITE SUPERVISOR SHALL ATTEND A MEETING ON SITE FOR DRAWING REVIEW AND PROJECT EXPECTATIONS.



Remove existing brick paving to dimensions shown and salvage for re-use. Remove subgrade leaving a 3" banding of compacted subgrade around pavers to receive edge restraint, see detail. Remove soil and debris to a depth of 2', sloping side walls of hole at 60d angle. Backfill with bioretention media, see notes. Leave finish grade of soil 2" below bottom of edge restraint in center of planter

Hull Street Road

66± PUBLIC R/W



For Permit	
Revision Block	
Revised per city comment 11.18.25	
Date: 12-8-25	Sheet 2 of 7

Greening Richmond Public Libraries

IMPROVING THE HEALTH OF THE JAMES RIVER BY REDUCING STORMWATER POLLUTION

Hull Street Branch Library

1400 Hull Street Road, Richmond, 23224

LEGEND

- AC UNIT
- BOLLARD
- ELEC. BOX
- ELEC. METER
- GAS METER
- GAS VALVE
- LIGHT POLE
- SIGN
- TELE. PED.
- WATER METER
- ELEC. TRANSFORMER
- ADA PARKING
- UTILITY POLE
- IRRIGATION VALVE BOX
- 1X1 DROP INLET
- STORM MH
- CLEAN OUT
- FIBER HANDHOLE
- TRAFFIC HANDHOLE
- TRAFFIC LIGHT POLE
- WATER VALVE

- U.G. WATER
- U.G. GAS
- O.H. TELEPHONE
- CONCRETE

- Downspout locations
- Downspout location, goes below ground
- 4" PVC irrigation conduit
- Main sewer line
- Silt Fence, see detail
- Limits of Disturbance

Proposed Elements, see details

- Permeable Pavers
- Concrete
- Artificial Turf
- Bioretention Basin

NOTES

THE EXISTENCE AND LOCATION OF UNDERGROUND UTILITIES ARE ONLY PARTIALLY SHOWN ON THIS PLAN. CONTACT MISS UTILITY.

CONTRACTOR TO ASSUME ALL RESPONSIBILITY FOR CONSTRUCTION METHODS EMPLOYED AND FIELD VERIFY ALL DIMENSIONS. ISSUES AND CONCERNS SHALL BE REPORTED TO FOUR WINDS.

CONTRACTOR TO ENSURE POSITIVE DRAINAGE AWAY FROM ALL BUILDINGS AT ALL TIMES DURING THE DEMOLITION AND BUILDING PROCESS.

NO PUBLIC THROUGHFARES INCLUDING SIDEWALKS SHALL BE BLOCKED DURING DEMOLITION OR CONSTRUCTION WITHOUT PROPERLY DISPLAYED MUNICIPALITY PERMITS. NO HOLES SHALL BE LEFT OPEN OVERNIGHT WITHOUT SECURING PERIMETER FENCING OR INSTALLING CAUTION TAPE AROUND THE HOLE.

CONTRACTOR TO OBTAIN ALL BUILDING PERMITS, SOIL STUDIES, AND STRUCTURAL DETAILS AS REQUIRED BY THE MUNICIPALITY.

*ALL EXCAVATED SOILS INCLUDING ORGANICS SUCH AS MINIMAL MULCH AND REMOVED TURF SHALL BE USED TO BUILD THE MOUND. SEE LAYOUT PLAN. EXCAVATED GRAVEL AT 1" OR SMALLER FROM THE EXISTING OLD ROADBED MAY ALSO BE USED BUT SHALL BE PLACED AT THE BOTTOM OF THE MOUND. SEE NOTES ON LAYOUT PLAN FOR FULL CONSTRUCTION METHOD.

IRRIGATION SYSTEM BY RICHMOND IRRIGATION AND MANAGED BY LANDSCAPE ARCHITECT. FOLLOW CONDUIT LOCATIONS AND SALVAGE EXISTING COMPONENTS WHERE POSSIBLE DURING DEMOLITION.

CONTRACTOR TO ALLOW ONE WEEK IN PROJECT SCHEDULE FOR ROUGH IN OF IRRIGATION SYSTEM. CONTRACTOR MAY BE ON SITE BUT MUST STAY OUT OF THE WAY (ALIGN WITH CONCRETE POUR/MASONRY/PAVERS, ORNAMENTAL GRAVEL, ARBOR SCHEDULE, ETC).

CONTRACTOR TO DOCUMENT DEPTHS OF BASIN EXCAVATION AND EXPLORATORY EXCAVATION (STORMWATER INFRASTRUCTURE EXPOSURE) WITH PHOTOS IN REAL TIME. UPLOAD TO DROPBOX WITH LINK PROVIDED BY LANDSCAPE ARCHITECT.

COMPREHENSIVE GRADING PLAN INCLUDING CRITICAL SPOT ELEVATIONS PROVIDED WITH CONSTRUCTION DOCUMENTS.

THIS DRAWING PRINTS TO SCALE ON 24 X 36" PAPER AND SHOULD BE PRINTED IN COLOR. DO NOT USE NOT-TO-SCALE OR BLACK AND WHITE DRAWINGS FOR FIELD WORK OR CONSTRUCTION.

UPON BID AWARD CONTRACTOR'S PROJECT MANAGER, FOREMAN, AND/OR SITE SUPERVISOR SHALL ATTEND A MEETING ON SITE FOR DRAWING REVIEW AND PROJECT EXPECTATIONS.

STORMWATER MANAGEMENT NARRATIVE

The existing site contains the library building, associated parking, sidewalks, a public art plaza and landscaping. Drainage generally runs away from the building toward the adjacent roadways. The parking lot drains to the alley, and then out to 14th Street. All drainage from the site and surrounding sidewalks is collected into the City's combined sewer system at the adjacent inlet on Hull Street or at the inlet on 14th Street at its intersection with Decatur Street.

The main objective of and purpose for this project is to provide improved aesthetics through landscaping enhancements that will reduce runoff, improve stormwater quality and promote infiltration. This will be achieved through the installation of an Urban Bio Retention Basin, permeable pavers and an artificial turf grassed area within the site. For purposes of this project, the site and adjacent City sidewalks to the back of existing curb will be used to define the site area.

Stormwater Quality Analysis:
While water quality treatment is not required due to the location in the combined sewer services area, calculations are provided to illustrate the impact of the improvements made on the site. As indicated by the VRRM calculations, if this project were required to meet the water quality standards, the design exceeds the requirements of 9VAC25-875-590 for water quality treatment on a ReDevelopment project. The TP Load Reduction Required is 0.03 lb/yr of Phosphorous. The Target TP Load Reduction is Exceeded by 0.02 lb/yr; a total of 0.05 lb/yr of Phosphorous will be removed from the site after the improvements.

Stormwater Quantity Analysis:
Due to the location of this site in the Combined Sewer Services area, the stormwater quantity analysis is based on Minimum Standard 19, which requires that the site be developed such that it will not cause the pre-development peak runoff rate from a ten-year storm to increase when runoff outfalls into a man-made channel, inclusive of sanitary sewer flow. In other words

$$(Q10pre + Qsan pre) \geq (Q10post + Qsan post)$$

For this project, there is no change to the sanitary sewer discharge, so the requirement is:

$$Q10pre \geq Q10post$$

This is achieved through the reduction of impervious area on the site and replacement with larger planting beds, addition of tree wells, an Urban Bioretention Basin in the sidewalk, an Artificial Turf outdoor space and replacement of existing asphalt with Permeable Pavers in the parking lot.

The resultant calculations show that the design is in compliance with MS-19 requirements:

$$Q10pre = 2.17 cfs \geq Q10post = 2.01 cfs$$

BMP SUMMARY

- BASIN 1: 30" BIO-RETENTION BASIN, VARIABLE WIDTH. SEE SHEET 4 FOR DETAIL, INCLUDING CURBING AND OVERFLOW, AND LANDSCAPE PLAN FOR VEGETATION REQUIREMENTS.
- BASIN 2: MICRO-INFILTRATION/ARTIFICIAL TURF. SEE SHEET 4 FOR DETAIL, INCLUDING EDGE RESTRAINTS. NOTE IMPERMEABLE LINER REQUIRED WITHIN 10' OF EXISTING BUILDING FOUNDATION.
- BASIN 3: MICRO-INFILTRATION/PERMEABLE PAVERS. SEE SHEET 4 FOR DETAIL, INCLUDING EDGE RESTRAINTS. NOTE IMPERMEABLE LINER REQUIRED WITHIN 10' OF EXISTING BUILDING FOUNDATION.

BMP MAINTENANCE REQUIREMENTS:

BASIN 1: P-FIL-05 BIORETENTION BASIN FIRST YEAR MAINTENANCE


Activity	Timing
Initial Inspections	For the first 6 months following construction, the site should be inspected at least twice after storm events that exceed 0.5 inch of rainfall.
Spot Reseeding	Inspectors should look for bare or eroding areas in the contributing drainage area or around the bioretention area, and make sure they are immediately stabilized with grass cover.
Fertilization	One-time, spot fertilization may be needed for initial plantings. Slow-release nitrogen sources should be utilized whenever possible.
Watering	Watering is needed once a week during the first 2 months, and then as needed during the first growing season (March/April-October), depending on rainfall.
Remove and replace dead plants	Since significant amounts of the initial planting stock may not survive in the first year, construction contracts should include a care-and-replacement warranty to ensure that vegetation is properly established and survives during the first growing season following construction. The typical thresholds below which replacement is required are 85% survival of intended/seeded herbaceous plant material and 100% survival of shrubs and trees.

P-FIL-05 BIORETENTION BASIN ROUTINE MAINTENANCE

Maintenance Tasks	Frequency
Mow grass filter strips and bioretention turfgrass cover.	At least 4 times per year
Perform spot weeding, erosion repair, trash removal, and mulch raking.	Monthly
Add reinforcement planting to maintain desired vegetation density. Remove invasive plants using recommended control methods. Stabilize the contributing drainage area to prevent erosion.	As needed
Perform spring inspection and cleanup. Supplement mulch to maintain a 2 to 3-inch layer. Prune trees and shrubs.	Annually as/iff needed
Remove sediment in pretreatment cells and inflow points.	At least 4 times per year
Replace the mulch layer.	Every 2-3 years or if in poor condition
Reevaluate Ksat via appropriate method for both primary media filter layer and underlying and/or lateral soil infiltration zone (if utilized).	Every 5 years

BASINS 2 & 3: P-FIL-04 INFILTRATION ROUTINE MAINTENANCE

Maintenance Activity	Schedule
Replace pea gravel/topsoil and top surface filter fabric (when clogged). Non-vegetated filter strips as necessary and remove the clippings.	As needed
Ensure that the contributing drainage area, inlets, and facility surface are clear of debris.	Quarterly
Ensure that the contributing drainage area is stabilized. Remove sediment and oil/grease from pretreatment devices, as well as from overflow structures. Repair undercut and eroded areas at inflow and outflow structures.	Quarterly
Check observation wells 3 days after a storm event in excess of 1/2 inch in depth. Standing water observed in the well after 3 days is a clear indication of clogging.	Semi-annually
Inspect pretreatment devices and diversion structures for sediment build-up and structural damage. Remove trees that start to grow in the vicinity of the infiltration facility.	Annually
Clean out accumulated sediments from the pretreatment cell.	Annually



DA C
0.044 AC C=0.70

DA B
0.043 AC C=0.79

DA A
0.037 AC C=0.72

For Permit

Revision Block
Revised per city comment 11.18.25

Date: 12-8-25
Sheet: 3 of 7



Grading Plan
For construction






Greening Richmond Public Libraries

IMPROVING THE HEALTH OF THE JAMES RIVER BY REDUCING STORMWATER POLLUTION

Hull Street Branch Library





1400 Hull Street Road, Richmond, 23224



BASIN 1 - BIORETENTION
NO SCALE

BASIN 2 - MICRO INFILTRATION - ARTIFICIAL TURF
NO SCALE

BASIN 3 - MICRO INFILTRATION - PERMEABLE PAVERS
NO SCALE






ADA RAMP SECTION
NO SCALE

STRUCTURED EDGE ALUMINUM PAVES RESTRAINT
NO SCALE

DECORATIVE FENCE
NO SCALE

ADA RAMP WALLS
NO SCALE



CONCRETE WALKS AND PATIO
NO SCALE

GENERATOR FENCE CLADDING
NO SCALE

PAVERS, DRY LAID
NO SCALE



For Permit

Revision Block	
Revised per city comment 11.18.25	

Details For construction

Date: 12-8-25 Sheet 4 of 7

Scale: 1" = 12'

Greening Richmond Public Libraries

IMPROVING THE HEALTH OF THE JAMES RIVER BY REDUCING STORMWATER POLLUTION

Hull Street Branch Library

1400 Hull Street Road, Richmond, 23224

Greening Richmond Public Libraries: DCR Bioretention Design Standards Compliance, Hull Street Branch


BMP	DCR Design Standard	Sizing	Ponding Depth	Media Depth	Gravel Sump Depth	Calculated Storage Depth	Infiltration Rate	Underdrain	Geometry	Pre-treatment	Conveyance	Planting	Setbacks
Basin 1 Urban BioRetention	Table 9-A.2, Level One	CDA= 1097 sq ft impervious, 541 pervious 46 sq ft required, 152 sq ft provided	3"	30"	12"	1.275	< .57/hr	6" per PVC	one cell design SFP/L ratio 0.3 or greater	Energy Dissipater, 2 depth grass like plantings	on-line, sheet flow	>75% coverage in 2 yrs	2' from curb & paving no utilities this area
Basin 2 Micro Infiltration (Artificial Turf)	Table 8.2 Level One	CDA= 1491 sq ft impervious, 387 pervious 46 sq ft required, 152 sq ft provided	-	5"	12"	0.504	< .57/hr	None	one cell design	Perimeter Planting bed	sheet flow	-	Impervious liner within 10' of foundation
Basin 3 Micro Infiltration (Perm. Pavers)	Table 8.2 Level One	CDA= 1227 sq ft Pavers, 683 pervious 149 sq ft required, 1227 sq ft provided	-	5"	12"	0.504	< .57/hr	None	one cell design	Perimeter Planting bed	surface/sheet flow	-	Impervious liner within 10' of foundation

Runoff coefficients are .95 for impervious roof or pavement and .4 for planting bed, turf and perm. pavers

Basin 1	Basin 2	Basin 3
SA = (TV (91.76)/ 2 ft) = 45.88 TV impervious = (.45 x 1097 sq ft CDA)/ 12 = 86.69 TV pervious = (.4 x 152 sq ft CDA)/ 12 = 5.07	SA = (TV (150.94)/(0.41 + 0.33*2) = 148.11 TV impervious = (.45 x 1491 sq ft CDA)/ 12 = 118.04 TV pervious = (.4 x 387 sq ft CDA)/ 12 = 12.90	SA = (TV (63.67)/(0.41 + 0.33*2) = 60.07 TV Pavers = (.40 x 1227 sq ft CDA)/ 12 = 40.90 TV pervious = (.40 x 683 sq ft CDA)/ 12 = 22.77
Calc Depth = 3" ponding @ 100%+2.5@25%+1@40%	Calc Depth=5" sand@25%+1@40%	Calc Depth=5" Pavers@25%+1@40%

*soil type is not known for due to inaccessible soils below existing pavement, therefore the lowest infiltration rates have been used

SOILS MAP + DATA



*NOTE: NO FORMAL CONSTRUCTION ENTRANCE IS PROPOSED. INFORMATION IS INCLUDED IN THE EVENT OF SEDIMENTATION OF THE STREET AND/OR GUTTER DURING CONSTRUCTION

MAP UNIT LEGEND

MAP UNIT SYMBOL MAP UNIT NAME
41 URBAN LAND

EROSION AND SEDIMENT CONTROL MAINTENANCE

ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CHECKED DAILY AND AFTER EACH RUNOFF PRODUCING RAINFALL EVENT BY THE REGISTERED LAND DISTURBER (RLD) LISTED ON THE PERMIT FOR THIS PROJECT. ANY NECESSARY REPAIRS OR REPLACEMENTS SHALL BE MADE BY THE CONTRACTOR IMMEDIATELY. ALL SEDIMENT REMOVED FROM EROSION CONTROL PRACTICES SHALL BE DISPOSED OF IN AN AREA PROTECTED FROM EROSION.

C-SCM-03 CONSTRUCTION ENTRANCE
1. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE OR THE WASHING AND REWORKING OF EXISTING STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY STRUCTURES USED TO TRAP SEDIMENT.
2. ALL MATERIALS SPOILED, DROPPED, WASHED, OR TRACKED FROM VEHICLES ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED IMMEDIATELY.
3. THE USE OF WATER TRUCKS TO REMOVE MATERIALS DROPPED, WASHED, OR TRACKED ONTO ROADWAYS WILL NOT BE PERMITTED UNDER ANY CIRCUMSTANCES.

C-PCM-04 SILT FENCE
1. SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.
2. CLOSE ATTENTION SHALL BE PAID TO THE REPAIR OF DAMAGED SILT FENCE RESULTING FROM END RUNS AND UNDERCUTTING.
3. SHOULD THE FABRIC ON A SILT FENCE DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER STILL BE NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY.
4. SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH STORM EVENT. THEY MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER.
5. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM WITH THE EXISTING GRADE, PREPARED AND SEEDED.

EROSION AND SEDIMENT CONTROL NARRATIVE

A. PROJECT DESCRIPTION:
THIS PROJECT REQUIRES MINOR DEMOLITION AND GRADING APPROPRIATE FOR THE CONSTRUCTION OF SEVERAL BIORETENTION BASINS, INFILTRATION BASIN, PERVIOUS PAVERS AND LANDSCAPING IMPROVEMENTS. THE TOTAL DISTURBED AREA WILL BE APPROXIMATELY 0.15 AC.

B. EXISTING SITE CONDITIONS:
THE EXISTING SITE CONTAINS THE EXISTING LIBRARY BUILDING, CONCRETE, BRICK AND ASPHALT PAVING, AND LANDSCAPING. EXISTING DRAINAGE ON THE SITE RUNS GENERALLY AWAY FROM THE BUILDING AND TOWARD THE ADJACENT STREETS.

C. ADJACENT AREAS:
THE ADJACENT PARCELS ARE COMMERCIAL AND RESIDENTIAL IN NATURE. THE SITE IS BOUNDED ON THE NORTH AND EAST BY PUBLIC ROADWAY, AND TO THE WEST AND SOUTH BY VACANT COMMERCIAL AND RESIDENTIAL PROPERTIES. THERE DOES NOT APPEAR TO BE ANY OFFSITE DRAINAGE COMING ONTO THE SITE.

D. OFF-SITE AREAS:
THIS PROJECT WILL NOT ADVERSELY IMPACT OFF SITE AREAS. IF OFF-SITE BORROW MATERIAL IS REQUIRED TO COMPLETE THE WORK, OR IF THE CONSTRUCTION RESULTS IN EXCESS SOIL MATERIALS THAT CANNOT BE USED ONSITE, THE CONTRACTOR IS RESPONSIBLE FOR ENSURING PROPER EROSION CONTROL MEASURES AND PERMITS ARE IN PLACE, FUNCTIONAL, AND MAINTAINED AT BORROW OR SPOIL SITE LOCATIONS.

E. SOILS:
ACCORDING TO USDA SOIL SURVEY SOIL IN THE AREA OF THE PROPOSED CONSTRUCTION IS 41 URBAN LAND. SOIL CLASSIFICATION IS HYDROLOGIC GROUP B, WELL DRAINED WITH A MODERATE EROSION FACTOR. VISUAL INSPECTION OF THE SITE INDICATES THAT THE SOIL DOES NOT APPEAR TO BE PARTICULARLY SUSCEPTIBLE TO EROSION. ON-SITE SOIL TESTING IS NOT POSSIBLE DUE TO EXISTING PAVING. THE LOWEST INFILTRATION RATE WAS USED FOR DESIGN.

F. CRITICAL AREAS:
THERE DOES NOT APPEAR TO BE ANY CRITICAL EROSION AREAS ON THE SITE. HOWEVER, THE SITE WILL BE PROTECTED FROM SOIL LOSS AT ALL TIMES DURING CONSTRUCTION.

G. EROSION & SEDIMENT CONTROL MEASURES:
SILT FENCE BARRIER - C-PCM-04: SILT FENCE SEDIMENT BARRIERS SHALL BE PROVIDED DOWNSLOPE OF AREAS WITH MINIMAL GRADES TO FILTER SEDIMENT LADEN RUNOFF FROM SHEET FLOW AS INDICATED.

H. PERMANENT STABILIZATION:
AREAS NOT PAVED OR LANDSCAPED WILL BE MULCHED ACCORDING TO THE VIRGINIA STORMWATER MANAGEMENT HANDBOOK REQUIREMENTS AS INDICATED ON THE LANDSCAPE PLAN.

I. STORMWATER RUN-OFF CONSIDERATIONS:
THIS SITE LIES WITHIN THE CITY'S COMBINED SEWER SERVICE AREA, WHILE NOT REQUIRED, STORMWATER QUALITY TREATMENT IS PROVIDED ONSITE THROUGH BIORETENTION BASINS AND OTHER INFILTRATION MEASURES. STORMWATER QUALITY CONTROL IS PROVIDED WITH REDUCED IMPERVIOUSNESS OF THE SITE, AND WITHIN THE SUBBASE ON THE BMPs AND THROUGH INFILTRATION AND DISCHARGE CONTROL DEVICES.

THE DISTURBED AREA OF THE SITE WILL BE LESS THAN ONE ACRE.
THE SITE LIES WITHIN ZONE X PER FEMA MAP #510129 0039F (JULY 8, 2025)

J. CALCULATIONS:
WATER QUALITY: WHILE THERE IS NO REQUIRED PHOSPHOROUS REMOVAL RATE DUE TO LOCATION WITHIN THE COMBINED SERVICES AREA, 0.05 LB/RYR PHOSPHOROUS REDUCTION IS ACHIEVED.

WATER QUANTITY: THE POINT OF ANALYSIS IS THE LOCATION WHERE THE DRAINAGE AREA ENTERS THE CITY STORM SEWER SYSTEM. THE SITE RUNOFF IS REDUCED DUE TO A REDUCTION IN IMPERVIOUS AREA AS WELL AS THE INSTALLATION OF ON-SITE INFILTRATION MEASURES.

CONSTRUCTION SEQUENCE

- PHASE I:**
- THE OWNER SHALL GIVE THE INSPECTOR 48 HOURS NOTIFICATION TO SCHEDULE AN ON-SITE PRE-CONSTRUCTION MEETING FOR THE ISSUANCE OF A LAND DISTURBANCE PERMIT. THE CERTIFIED RESPONSIBLE LAND DISTURBER (CRLD) MUST ATTEND THE PRE-CONSTRUCTION MEETING.
 - INSTALL STORM DRAIN INLET PROTECTION AND SILT FENCING AS THE FIRST MEASURE OF CONSTRUCTION OPERATIONS.
 - INSTALL BARRIERS TO INFILTRATION AREAS (ORANGE SNOW FENCING) TO KEEP CONSTRUCTION TRAFFIC FROM TRAVERSING THOSE AREAS DURING CONSTRUCTION.
 - BEGIN SITE DEMOLITION ONCE EROSION CONTROL MEASURES ARE IN PLACE.
 - BEGIN SITE GRADING OPERATIONS.
 - BRING THE SITE TO SUB-GRADE ELEVATIONS AND PROVIDE SMOOTH GRADES.
- PHASE II:**
- BEGIN SITE DEVELOPMENT OPERATIONS INCLUDING BMP CONSTRUCTION, ADA RAMP, LANDSCAPE AND HARDSCAPE IMPROVEMENTS, ETC.
 - INSTALL PAVING, CURBING, SIDEWALKS, SITE FENCING, AND SIGNAGE ETC.
 - INSTALL VEGETATION AND GROUND COVER IN LANDSCAPED AREAS.
 - AS THE SITE REACHES FINAL GRADE IN UNPAVED AREAS, INSTALL MULCHING/GROUND COVER AS SOON AS POSSIBLE.
 - CONTROL SEDIMENT LADEN RUNOFF FROM REACHING ROAD AND/OR GUTTER PAN MAINTAINED UNTIL THERE IS NO LONGER A THREAT TO TRANSPORT SOIL FROM THE CONSTRUCTION SITE.
 - REMOVE EROSION CONTROL MATERIALS ONLY AFTER OBTAINING APPROVAL FROM THE CITY EMS INSPECTOR. SITE IS FULLY STABILIZED AND THERE IS NO LONGER A THREAT OF SOIL EROSION FROM THE SITE.

STORMWATER SUMMARY

THE REDUCTION IN IMPERVIOUS AREA RESULTS IN A REDUCTION IN RUNOFF FROM THE SITE IN ACCORDANCE WITH SW623-875-600 AND MS-19. WATER QUALITY TREATMENT VOLUMES PROVIDED IN THE PROPOSED BMPs IS ADEQUATE TO REDUCE THE REQUIRED TP LOAD IN ACCORDANCE WITH SW623-875-600.

Site Results (Water Quality Compliance) VRRM 4.1, 2024

Area Checks	D.A. A	D.A. B	D.A. C	D.A. D	D.A. E	AREA CHECK
FOREST (ac)	0.00	0.00	0.00	0.00	0.00	OK
MIXED OPEN AREA TREATED (ac)	0.00	0.00	0.00	0.00	0.00	OK
MIXED OPEN AREA TREATED (ac)	0.00	0.00	0.00	0.00	0.00	OK
MANAGED TURF AREA (ac)	0.01	0.01	0.02	0.00	0.00	OK
MANAGED TURF AREA TREATED (ac)	0.00	0.01	0.00	0.00	0.00	OK
IMPERVIOUS COVER (ac)	0.03	0.03	0.03	0.00	0.00	OK
IMPERVIOUS COVER TREATED (ac)	0.03	0.03	0.03	0.00	0.00	OK
AREA CHECK	OK	OK	OK	OK	OK	

Site Treatment Volume (ft³)

1,029

Runoff Reduction Volume and TP By Drainage Area

	D.A. A	D.A. B	D.A. C	D.A. D	D.A. E	TOTAL
RUNOFF REDUCTION VOLUME ACHIEVED (ft³)	47	45	47	0	0	138
TP LOAD AVAILABLE FOR REMOVAL (lb/yr)	0.03	0.03	0.04	0.00	0.00	0.11
TP LOAD REDUCTION ACHIEVED (lb/yr)	0.02	0.02	0.02	0.00	0.00	0.05
TP LOAD REMAINING (lb/yr)	0.02	0.01	0.02	0.00	0.00	0.06
NITROGEN LOAD REDUCTION ACHIEVED (lb/yr)	0.22	0.29	0.22	0.00	0.00	0.72

Total Phosphorus

RINAL POST-DEVELOPMENT TP LOAD (lb/yr)	0.30
TP LOAD REDUCTION REQUIRED (lb/yr)	0.03
TP LOAD REDUCTION ACHIEVED (lb/yr)	0.05
TP LOAD REMAINING (lb/yr)	0.25
REMAINING TP LOAD REDUCTION REQUIRED (lb/yr)	0.00

** TARGET TP REDUCTION EXCEEDED BY 0.02 LB/YEAR **

Total Nitrogen (For Information Purposes)

POST-DEVELOPMENT LOAD (lb/yr)	4.09
NITROGEN LOAD REDUCTION ACHIEVED (lb/yr)	0.72
REMAINING POST-DEVELOPMENT NITROGEN LOAD (lb/yr)	3.37

Project Name: Greening RPL - Hull Street Library
Date: 12/9/2025
Linear Development Project? No

CLEAR ALL
(Ctrl+Shift+R)

data input cells
constant values
calculation cells
final results

Site Information

Post-Development Project (Treatment Volume and Loads)

Enter Total Disturbed Area (acres) → 0.36

Maximum reduction required:	10%
The site's net increase in impervious cover (acres) is:	0
Post-Development TP Load Reduction for Site (lb/yr):	0.03

Check:

BMP Design Specifications List: 2024 Stds & Specs
Linear project? No
Land cover areas entered correctly? ✓
Total disturbed area entered? ✓

Pre-ReDevelopment Land Cover (acres)

	A Soils	B Soils	C Soils	D Soils	Totals
Forest (acres) - undisturbed, protected forest or reforested land					0.00
Mixed Open (acres) - undisturbed/frequently maintained grass or shrub land					0.00
Managed Turf (acres) - disturbed, graded for yards or other turf to be mowed/managed			0.04		0.04
Impervious Cover (acres)			0.32		0.32
					0.36

Post-Development Land Cover (acres)

	A Soils	B Soils	C Soils	D Soils	Totals
Forest/Open Space (acres) - undisturbed, protected forest or reforested land					0.00
Mixed Open (acres) - undisturbed/frequently maintained grass or shrub land					0.00
Managed Turf (acres) - disturbed, graded for yards or other turf to be mowed/managed			0.08		0.08
Impervious Cover (acres)			0.28		0.28
Area Check	OK	OK	OK	OK	0.36

Post-Development Requirement for Site Area

TP Load Reduction Required (lb/yr) 0.03

Nitrogen Loads (Informational Purposes Only)

Pre-ReDevelopment TN Load (lb/yr) 4.26

Final Post-Development TN Load 4.09

LAND COVER SUMMARY -- PRE-REDEVELOPMENT

Pre-ReDevelopment	Land Cover Summary-Pre	
	Listed	Adjusted ¹
Forest Cover (acres)	0.00	0.00
Weighted Rv(forest)	0.00	0.00
Weighted Loading Rate(forest)	0.00	0.00
% Forest	0%	0%
Mixed Open Cover (acres)	0.00	0.00
Weighted Rv(mixed)	0.00	0.00
Weighted Loading Rate(mixed)	0.00	0.00
% Mixed Open	0%	0%
Managed Turf Cover (acres)	0.04	0.04
Weighted Rv(turf)	0.22	0.22
Weighted Loading Rate(turf)	0.75	0.75
% Managed Turf	11%	11%
Impervious Cover (acres)	0.32	0.32
Rv(impervious)	0.95	0.95
Weighted Loading Rate(impervious)	0.86	0.86
% Impervious	89%	89%
Total Site Area (acres)	0.36	0.36
Site Rv	0.87	0.87

Treatment Volume and Nutrient Load

Pre-ReDevelopment Treatment Volume (acre-ft)	0.0261	0.0261
Pre-ReDevelopment Treatment Volume (cubic feet)	1,135	1,135
Pre-ReDevelopment TP Load (lb/yr)	0.30	0.30
Pre-ReDevelopment TP Load per acre (lb/acre/yr)	0.85	0.85
Baseline TP Load (lb/yr) (0.26 lb/acre/yr applied to pre-redevelopment area excluding pervious land proposed for new impervious cover)		0.09

LAND COVER SUMMARY -- POST DEVELOPMENT

Post-ReDevelopment	Land Cover Summary-Post (Final)		Land Cover Summary-Post Post-Development New Impervious
	Post ReDev. & New Impervious	Post-Development	
Forest Cover (acres)	0.00	0.00	
Weighted Rv(forest)	0.00	0.00	
Wgt. Ld. Rate(forest)	0.00	0.00	
% Forest	0%	0%	
Mixed Open Cover (acres)	0.00	0.00	
Weighted Rv(mixed)	0.00	0.00	
Wgt. Ld. Rate(mixed)	0.00	0.00	
% Mixed Open	0%	0%	
Managed Turf Cover (acres)	0.08	0.08	
Weighted Rv(turf)	0.22	0.22	
Wgt. Ld. Rate(turf)	0.75	0.75	
% Managed Turf	22%	22%	
Impervious Cover (acres)	0.28	0.28	
Rv(impervious)	0.95	0.95	
Wgt. Ld. Rate(imperv.)	0.86	0.86	
% Impervious	78%	78%	
Final Site Area (acres)	0.36	0.36	
Final Post Dev Site Rv	0.79	0.79	

Treatment Volume and Nutrient Load

Final Post-Development Treatment Volume (acre-ft)	0.0236	0.0236	Post-Development Treatment Volume (acre-ft)	-
Final Post-Development Treatment Volume (cubic feet)	1,029	1,029	Post-Development Treatment Volume (cubic feet)	-
Final Post-Development TP Load (lb/yr) [*]	0.30	0.30	Post-Development TP Load (lb/yr)	-
Final Post-Development TP Load per acre (lb/acre/yr)	0.83	0.83	Post-Development TP Load per acre (lb/acre/yr)	0.83
Max. Reduction Required (Below Pre-Development Load)		10%		


¹ Adjusted Land Cover Summary:
Pre-ReDevelopment land cover minus pervious land cover (forest, mixed open or managed turf) acreage proposed for new impervious cover.

Adjusted total acreage is consistent with Post-Development acreage (minus acreage of new impervious cover).

Column 1 shows load reduction requirement for new impervious cover (based on new development load limit, 0.26 lb/acre/year).



Details
For construction



For Permit

Revision Block
Revised per city comment 11.18.25

Date: 12-8-25
Sheet 5 of 7

Greening Richmond Public Libraries

IMPROVING THE HEALTH OF THE JAMES RIVER BY REDUCING STORMWATER POLLUTION

Hull Street Branch Library

1400 Hull Street Road, Richmond, 23224

LEGEND

- BOLLARD
- △ E-BL-S
- ⊕ GAS METER
- Ⓜ TELE. PED.
- ⊙ TREE
- ⚡ FIRE HYDRANT
- ⊙ BUSH
- ⊙ TRAFFIC LIGHT POLE
- ♿ ADA PARKING
- ⊕ SEWER CLEAN OUT
- ⊠ ELEC. BOX
- ⊙ STORM MH
- U.G. WATER
- U.G. GAS
- O.H. ELECTRIC

- Main sewer line
- Existing Trees & Shrubs To Be Preserved:

NOTES

THE EXISTENCE AND LOCATION OF UNDERGROUND UTILITIES ARE ONLY PARTIALLY SHOWN ON THIS PLAN. CONTACT MISS UTILITY.

CONTRACTOR TO ASSUME ALL RESPONSIBILITY FOR CONSTRUCTION METHODS EMPLOYED AND FIELD VERIFY ALL DIMENSIONS. ISSUES AND CONCERNS SHALL BE REPORTED TO FOUR WINDS.

CONTRACTOR TO ENSURE POSITIVE DRAINAGE AWAY FROM ALL BUILDINGS AT ALL TIMES DURING THE DEMOLITION AND BUILDING PROCESS.

NO PUBLIC THOROUGHFARES INCLUDING SIDEWALKS SHALL BE BLOCKED DURING DEMOLITION OR CONSTRUCTION WITHOUT PROPERLY DISPLAYED MUNICIPALITY PERMITS. NO HOLES SHALL BE LEFT OPEN OVERNIGHT WITHOUT SECURING PERIMETER FENCING OR INSTALLING CAUTION TAPE AROUND THE HOLE.

CONTRACTOR TO OBTAIN ALL BUILDING PERMITS, SOIL STUDIES, AND STRUCTURAL DETAILS AS REQUIRED BY THE MUNICIPALITY.


IRRIGATION SYSTEM BY RICHMOND IRRIGATION AND MANAGED BY LANDSCAPE ARCHITECT. FOLLOW CONDUIT LOCATIONS AND SALVAGE EXISTING COMPONENTS WHERE POSSIBLE DURING DEMOLITION.

CONTRACTOR TO ALLOW ONE WEEK IN PROJECT SCHEDULE FOR ROUGH IN OF IRRIGATION SYSTEM. CONTRACTOR MAY BE ON SITE BUT MUST STAY OUT OF THE WAY (ALIGN WITH CONCRETE POUR/MASONRY/PAVERS, ORNAMENTAL GRAVEL, ARBOR SCHEDULE, ETC).


THIS DRAWING PRINTS TO SCALE ON 24 X 36" PAPER AND SHOULD BE PRINTED IN COLOR. DO NOT USE NOT-TO-SCALE OR BLACK AND WHITE DRAWINGS FOR FIELD WORK OR CONSTRUCTION.

PLANTS, SOIL AMENDMENTS, AND MULCH WILL BE INSTALLED BY VOLUNTEERS.

Code	Botanical Name	Common Name	Quantity	Size	Mature Height
AR	Acer rubrum	Red Maple	2	14-16'	40'
CV	Chionanthus virginicus 'Spring Fleecing'	Fringetree	2	6-8'	12'
CR	Cimifuga racemosa	Snakeroot	4	1 Gal	2.5'
DI	Dryopteris intermedia	Fancy Fern	20	1 Gal	2'
HA	Hydrangea arborescens	Smooth Hydrangea	8	5 Gal	4'
IV	Ilex vomitoria 'Bordeaux'	Dwarf Yaupon Holly	13	7 Gal	3'
IT1	Itea virginica 'Little Henry'	Sweetspire	14	3 Gal	3'
IT2	Itea virginica 'Scentlandia'	Sweetspire	15	3 Gal	2.5'
MV	Magnolia virginiana	Sweetbay Magnolia	5	8-10'	20'
NS	Nyssa sylvatica	Tupelo	1	12-14'	40'
PV1	Panicum virgatum 'Cape Breeze'	Switchgrass	60	1 Gal	3'
PV2	Panicum virgatum 'Shenandoah'	Switchgrass	31	3 Gal	3.5'
SS	Schizachyrium scoparium 'Standing Ovation'	Little Bluestem	175	1 Gal	2.5'
VD	Viburnum dentatum	Arrowwood Viburnum	3	7 Gal	5'




- GENERAL NOTES:
- THOROUGHLY TILL IN PLANTING SOIL MIXTURE AMENDMENTS TO DEPTH OF 8" IN ENTIRE GROUND COVER BED AREA.
 - WORK SOIL TO LOOSE, UNIFORM FINE TEXTURE.
 - HAND-TAMP BACKFILL TO REMOVE VOIDS AND AIR POCKETS.
 - WATER IMMEDIATELY AFTER PLANTING UNTIL NO MORE WATER IS ABSORBED.




○ Shrub Planting
Scale: none


○ Perennial Planting
Scale: none



○ Tree Planting
Scale: none



○ Planting Bed Edge
Scale: none



CITY OF RICHMOND ESTABLISHED 1737


SITE PLAN APPROVED

Kim J. Vande

DIRECTOR 01/22/2026



Planting Plan for
Volunteers
For construction



For Permit

Revision Block
Revised per city comment 11.18.25

Date: 12-8-25 Sheet 6 of 8

Greening Richmond Public Libraries

IMPROVING THE HEALTH OF THE JAMES RIVER BY REDUCING STORMWATER POLLUTION

Hull Street Branch Library

1400 Hull Street Road, Richmond, 23224

VESCH GENERAL EROSION AND SEDIMENT CONTROL NOTES

- ES-1: UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED AND MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA STORMWATER MANAGEMENT HANDBOOK AND THE VIRGINIA EROSION AND SEDIMENT CONTROL REGULATIONS 9VAC25-875.
- ES-2: THE PLAN APPROVING AUTHORITY MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITY, AND ONE WEEK PRIOR TO THE FINAL INSPECTION.
- ES-3: ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN CLEARING.
- ES-4: A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
- ES-5: PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING, BUT NOT LIMITED TO, OFF-SITE BORROW OR WASTE AREAS), THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY EROSION CONTROL PLAN TO THE OWNER FOR REVIEW AND APPROVAL BY THE PLAN APPROVING AUTHORITY.
- ES-6: THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE PLAN APPROVING AUTHORITY.
- ES-7: ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBING ACTIVITIES AND DURING SITE DEVELOPMENT UNTIL FINAL STABILIZATION IS ACHIEVED.
- ES-8: DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO AN APPROVED FILTERING DEVICE.
- ES-9: THE CONTRACTOR SHALL INSPECT ALL EROSION CONTROL MEASURES PERIODICALLY AND AFTER EACH RUNOFF-PRODUCING RAINFALL EVENT. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE IMMEDIATELY.

RICHMOND STANDARD E&S NOTES

1. PERMANENT OR TEMPORARY SOIL STABILIZATION SHALL BE APPLIED TO DENUEDD AREAS WITHIN SEVEN DAYS AFTER FINAL GRADE IS REACHED ON ANY PORTION OF THE SITE. TEMPORARY SOIL STABILIZATION SHALL BE APPLIED WITHIN SEVEN DAYS TO DENUEDD AREAS THAT MAY NOT BE AT FINAL GRADE, BUT WILL REMAIN DORMANT FOR LONGER THAN 14 DAYS. PERMANENT STABILIZATION SHALL BE APPLIED TO AREAS THAT ARE TO BE LEFT DORMANT FOR MORE THAN ONE YEAR.
2. EXCESS EXCAVATION DISPOSED OF OFF THE SITE SHALL BE DISPOSED OF IN ACCORDANCE WITH THE VIRGINIA STORMWATER MANAGEMENT HANDBOOK.
3. EROSION AND SEDIMENT CONTROLS SHALL BE INSTALLED IN ACCORDANCE WITH VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND SHALL BE PLACED PRIOR TO OR AS THE FIRST STEP OF THE LAND DISTURBING ACTIVITY.
4. EROSION AND SEDIMENT CONTROLS SHALL BE MAINTAINED SO THAT THE SEDIMENT CARRYING RUNOFF FROM THE SITE WILL NOT ENTER STORM DRAINAGE FACILITIES.
5. EROSION AND SEDIMENT CONTROLS SHALL BE MAINTAINED UNTIL THE DISTURBED AREA IS STABILIZED.
6. PROPERTIES ADJOINING THE SITE SHALL BE KEPT CLEAN OF MUD OR SILT CARRIED FROM THE SITE BY VEHICULAR TRAFFIC OR RUNOFF.
7. THE DISPOSAL OF WASTE MATERIALS REMOVED FROM EROSION AND SEDIMENT CONTROL FACILITIES AND THE DISPOSAL OF THESE FACILITIES SHALL BE IN ACCORDANCE WITH THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK.
8. STABILIZATION MEASURES SHALL BE APPLIED TO EARTHEN STRUCTURES SUCH AS DAMS, DIKES AND DIVERSIONS IMMEDIATELY AFTER INSTALLATION.
9. DURING CONSTRUCTION OF THE PROJECT, SOIL STOCKPILES SHALL BE STABILIZED OR PROTECTED WITH SEDIMENT TRAPPING MEASURES. THE APPLICANT IS RESPONSIBLE FOR THE TEMPORARY PROTECTION AND PERMANENT STABILIZATION OF ALL SOIL STOCKPILES ON SITE AS WELL AS SOIL INTENTIONALLY TRANSPORTED FROM THE PROJECT SITE.
10. ALL STORM SEWER INLETS THAT ARE MADE OPERABLE DURING CONSTRUCTION SHALL BE PROTECTED SO THAT SEDIMENT-LADEN WATER CANNOT ENTER THE CONVEYANCE SYSTEM WITHOUT FIRST BEING FILTERED OR OTHERWISE TREATED TO REMOVE SEDIMENT.
11. BEFORE NEWLY CONSTRUCTED STORMWATER CONVEYANCE CHANNELS OR PIPES ARE MADE OPERABLE, ADEQUATE OUTLET PROTECTION AND ANY REQUIRED TEMPORARY OR PERMANENT CHANNEL LINING SHALL BE INSTALLED IN BOTH THE CONVEYANCE CHANNEL AND RECEIVING CHANNEL.
12. WHEN WORK IN A LIVE WATERCOURSE IS PERFORMED, PRECAUTIONS SHALL BE TAKEN TO MINIMIZE ENCROACHMENT, CONTROL SEDIMENT TRANSPORT AND STABILIZE THE WORK AREA TO THE GREATEST EXTENT POSSIBLE DURING CONSTRUCTION. NONERODIBLE MATERIAL SHALL BE USED FOR THE CONSTRUCTION OF CAUSEWAYS AND COFFERDAMS. EARTHEN FILL MAY BE USED FOR THESE STRUCTURES IF ARMORED BY NONERODIBLE COVER MATERIALS.
13. WHEN A LIVE WATERCOURSE MUST BE CROSSED BY CONSTRUCTION VEHICLES MORE THAN TWICE IN ANY SIX-MONTH PERIOD, A TEMPORARY VEHICULAR STREAM CROSSING CONSTRUCTED OF NONERODIBLE MATERIAL SHALL BE PROVIDED.
14. ALL APPLICABLE FEDERAL, STATE AND LOCAL REQUIREMENTS PERTAINING TO WORKING IN OR CROSSING LIVE WATERCOURSES SHALL BE MET.
15. THE BED AND BANKS OF A WATERCOURSE SHALL BE STABILIZED IMMEDIATELY AFTER WORK IN THE WATERCOURSE IS COMPLETED.
16. UNDERGROUND UTILITY LINES SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING STANDARDS IN ADDITION TO OTHER APPLICABLE CRITERIA:
 - a. NO MORE THAN 500 LINEAR FEET OF TRENCH MAY BE OPENED AT ONE TIME.
 - b. EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES.
 - c. EFFLUENT FROM DEWATERING OPERATIONS SHALL BE FILTERED OR PASSED THROUGH AN APPROVED SEDIMENT TRAPPING DEVICE, OR BOTH, AND DISCHARGED IN A MANNER THAT DOES NOT ADVERSELY AFFECT FLOWING STREAMS OR OFF-SITE PROPERTY.
 - d. MATERIAL USED FOR BACKFILLING TRENCHES SHALL BE PROPERLY COMPACTED IN ORDER TO MINIMIZE EROSION AND PROMOTE STABILIZATION.
 - e. RESTABILIZATION SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THIS CHAPTER.
 - f. APPLICABLE SAFETY REQUIREMENTS SHALL BE COMPLIED WITH.

Greening Richmond Public Libraries Hull Street Branch Library Pre-Development Runoff Calculations			
Drainage Summary			
C Factor:			
Description	Area (ac)	C-factor	
Existing Impervious	0.229	0.90	
Existing Permeable	0.036	0.35	
Total	0.364	0.85	
Tc Calculations:			
Tc =	5.00 Min	(Minimum)	
I =	B		
(Ic + D)²			
I ₂ =	5.32 inHR		
I ₁₀ =	7.07 inHR		
I ₁₀₀ =	9.00 inHR		
Existing Runoff Conditions:	C-factor	Area	Q₁
	0.85	0.364	1.64
			2.17
			3.16

Greening Richmond Public Libraries Hull Street Branch Library Post-Development Runoff Calculations			
Drainage Summary			
C Factor:			
Description	Area (ac)	C-factor	
Proposed Impervious	0.224	0.90	
Proposed Permeable	0.279	0.35	
Total	0.364	0.70	
Tc Calculations:			
Tc =	5.00 Min		
I =	B		
(Ic + D)²			
I ₂ =	5.32 inHR		
I ₁₀ =	7.07 inHR		
I ₁₀₀ =	9.00 inHR		
Existing Runoff Conditions:	C-factor	Area	Q₁
	0.70	0.364	1.51
			2.01
			3.19



Landscape Operations & Maintenance Manual

Overview & System Functions

The site improvements at the Richmond Public Libraries are designed to be ecologically responsible landscapes that infiltrate stormwater on site, provide habitat and educational value by planting native species, and serve as a model for future development. This commitment to ecosystem services is also reflected in the care and maintenance of the properties to ensure that plants survive, infiltration systems remain in good function, and resources needed for landscape care are minimized.

Each site will be equipped with an operations and maintenance manual that is specific to the plant species and site improvements found there; bound and laminated copies of this manual will be supplied to the third-party contractor responsible for RPL landscape maintenance while a copy of the manual will also reside at each branch in a designated location known to the branch manager. At the date of writing the site-specific manuals are not yet available as the projects have yet to be constructed. Branch managers and contractor will complete an Annual Inspection Checklist jointly at the start of each growing season. This completed checklist will be bound into the library branch copy of the O&M Manual for inspection by city parties as desired. See below for the Annual Inspection Checklist.

This manual is an abbreviated version that has been reviewed and adopted by Richmond City Council

Scope of Weekly Services

Lawn Mowing

At each visit the entirety of the lawn area shall be mowed with all clippings recycled back into the lawn. Care shall be taken not to blow lawn clippings into planting beds (mow from the perimeter into the interior blowing clippings toward the center). Lawn edges shall be string trimmed.

Weeding

At each visit a visual inspection of the planting beds shall be made with all debris and trash removed. Weeds outside of Bee Zones may be treated with herbicides at rates specified on the product used. Weeding within the Bee Zones must be done by hand with care taken not to damage plants. If in doubt as to whether a plant is a weed or not – particularly emerging perennials – consult with fellow workers or wait until the next visit.

Irrigation Inspection and Watering

At each visit the site shall be inspected for excessively wet areas that may indicate an irrigation leak or excessively dry areas that may indicate a non-functioning or improperly aimed head. Plant decline is another indicator of improper water amounts but do not assume that browned leaves indicate drought, it is also a sign of root rot due to excessive water. Workers shall report issues to the head of their company.

Bioretenation areas will require hand watering once a week over the first summer IF IT DOES NOT RAIN.

Check the rain gauge provided at each site (see site specific manuals for locations). On some sites, the bioretention basins are equipped with their own irrigation zone for use in the first year only and in emergency cases thereafter. If this is the case inspect the planting area for irrigation issues as one would any other planting bed.

Surface Cleaning/ Blowing

At each visit the site parking lots and sidewalks shall be cleaned of debris. All trash shall be separated from organic matter and disposed of. On some sites, a surface leaf composting area is provided. This is intended to reduce the amount of material that must leave the site and provide compost for future projects. See site specific manuals for pattern of site blow down to move leaves and organic matter to composting areas. Care shall be taken not to blow material into bioretention basins or onto pervious pavers.

Bioretention Basin Care

For the first six months following construction the site should be inspected at least twice after storm events in excess of a 1/2" inch of rainfall. Weekly inspections shall also include:

- Check for sediment buildup or a fine crust at curb cuts, inflow points, gravel diaphragms or pavement edges that prevents flow from getting into the bed and remove any sediment.
- Look for bare soil or sediment sources draining to the bioretention basin and stabilize them immediately. These may include bare or eroding lawn areas that should be spot reseeded. Scarify the soil, apply seed and erosion control elements such as straw or erosion control blanket as necessary. Contractor to collect and quantify materials and labor used in stabilization practices to be billed in the next billing cycle.
- Check the bioretention bed for evidence of mulch flotation, excessive ponding, dead plants or concentrated flows, and take appropriate remedial action. These actions may include replacing dead plants immediately or raking mulch back into place. If dead plants are encountered, remove the dead portion of the plant to the ground for appearance. Do not remove the root ball until the replacement plant is on site. Workers shall report the plant removal or (dead trees they cannot handle) to the head of their company. See below for plant replacement protocol.
- Check for clogged or slow-draining soil media, a crust formed on the top layer, inappropriate soil media, or other causes of insufficient filtering time, and restore proper filtration characteristics.
- If water remains on the surface for more than 48 hours after a storm, adjustments to the grading may be needed or underdrain repairs may be needed. Report ongoing issues to the head of the maintenance company. See scope of biannual services below.

Pervious Paver Care

For the first six months following construction the site should be inspected at least twice after storm events in excess of a 1/2" inch of rainfall. Weekly inspections shall also include:

- Remove all material and sediments from the paver surface.
- Check to make sure aggregate material from between the pavers has not blow up onto the surface. If it has, either remove it or sweep back into the joints with a broom.
- Inspect the condition of the observation well cap to make sure it has not been knocked off.
- Inspect the surface of the permeable pavement for evidence of sediment deposition, organic debris, staining or ponding that may indicate surface clogging. Look for areas of sediment intrusion such as mulch migrating onto the pavers. Remove material and dig a trench edge where the intrusion has occurred. Workers shall report ongoing issues to the head of their company.

Scope of Annual Services

Annual Inspection

Branch managers and contractor will complete an Annual Inspection Checklist jointly at the start of each growing season. This shall occur after all species have leafed out for the year. This completed checklist will be bound into the library branch copy of the O&M Manual for inspection by city parties as desired. Inspections shall include:

- Note any dead or severely damaged plants and replace with the same species and cultivar or with a species approved by the RPL Maintenance and Operations Facilities Manager. This includes denuded lawn areas that flow into bioretention basins. Expenditures of up \$200 per site per biannual season may be made at the discretion of the contractor and billed to RPL with a PO or invoice from the plant supplier. Expenditures in excess of \$200 per site per season must be approved by the RPL Maintenance and Operations Facilities Manager with a formal estimate. If specific plants have been replaced more than once and continue to die, consult a horticulturalist or landscape architect to identify the issue and provide new species selection. Confirm that 75% to 90% of vegetative cover is maintained in the bioretention basins and add reinforcement plantings to maintain the desired density if needed.

- Inspect the health of all trees on site, noting dead wood to be removed or signs of disease and damage. Note any issues on the annual inspection report. These issues shall be forwarded to the city arborists by the Branch Manager.
- Inspect the entirety of the site per the weekly scope of work.
- Inspect the mulch layer for a maximum of 3" of mulch that doesn't touch the trunks of any trees or shrubs nor be mounded up around perennials. Adjust accordingly. Note that annual re-mulching will occur once a year in the fall.
- Inspect the surface of the permeable pavement for evidence of sediment deposition, organic debris, staining or ponding that may indicate surface clogging. Look for areas of sediment intrusion such as mulch migrating onto the pavers.
- Inspect the structural integrity of the pavement surface, looking for signs of surface deterioration, such as slumping, cracking, spalling or broken pavers. Replace or repair affected areas, as necessary.
- Inspect the condition of the observation well and make sure it is still capped.
- Generally, inspect any contributing drainage area for any controllable sources of sediment or erosion.
- Inspect the surface of the permeable pavement for evidence of sediment deposition, organic debris, staining or ponding that may indicate surface clogging. Then, test sections by pouring water from a five gallon bucket to ensure they work. If any signs of clogging are noted, schedule paver cleaning or system overhaul. Cleaning shall be accomplished with a vacuum machine rated for pervious paver cleaning such as the Typhoon Surface and Joint Cleaner by Pavetech. If a qualified machine is not available the paving system has been built in such a way so that the pavers, 1" fine aggregate setting bed, and fine aggregate joint material can be replaced:
 - o Remove all pavers and set aside.
 - o Remove all 21A gravel joint and setting bed material. This is contained by mortared edge restraints and separated from lower gravel layers with filter fabric.
 - o With fine aggregates removed test the system as noted above. If issues persist contact a civil engineer or landscape architect for further exploration.
 - o Clean or replace filter fabric taking care not to allow sediment into lower layers.
 - o Replace setting bed, clean and lay pavers, and sweep with joint material.

Maintenance Duties

Contractor Selection and Contracts

The Director of The Richmond Public Libraries and his staff at his discretion shall select the maintenance contractor to take care of all RPL properties. Contracts shall include the contractor's DPOR license number, a copy of professional insurance, and hourly labor rate and narrative describing standard mark-ups on materials, if applicable. The remainder of the contract should reiterate the above or reference this document.

Additional Maintenance

The City of Richmond shall provide ongoing site maintenance for the following:

- Tree removal or tree pruning not accessible from the ground.
- Snow removal and ice treatment. No salt may be used in areas draining to Bee Zones.
- Maintenance of hardscapes and utilities.
- Dumpster service and maintenance / cleaning of dumpster enclosures and surrounding areas.
- Gutter/ roof cleaning as necessary in areas where downspouts drain to bioretention basins or pervious pavers



SITE PLAN APPROVED	
	
DIRECTOR	01/22/2026

For Permit

Revision Block
Revised per city comment 11.18.25

Date: Sheet
12-8-25 7 of 7

Notes
For construction

